

**COSTURI UNITARE (Euro) - Actualizare MASTER PLAN**

	Articol	Parametrii	UM	COSTURI UNITARE	
				Cap. 4	TOTAL investitie (preturi curente)
				Investitie baza	
				(Euro)	(Euro)
CANALIZARE	Statie epurare	0 ... 1000 LE	Euro / locuitor echivalent	260	332
		1000 ... 2000 LE		232	296
		2000 ... 3000 LE		211	269
		3000 ... 4000 LE		198	253
		4000 ... 5000 LE		188	240
		5000 ... 6000 LE		181	231
		6000 ... 7000 LE		175	223
		7000 ... 8000 LE		170	217
		8000 ... 9000 LE		166	212
		9000 ... 10000 LE		163	208
		10000 ... 20000 LE		158	202
		20000 ... 30000 LE		150	192
		30000 ... 40000 LE		135	172
		40000 ... 50000 LE		110	141
	Reabilitare SEAU	6000 ... 7000 LE	euro/ l.e.	82	105
	Retea canalizare (conducte, camine, racorduri)	Extindere	ml	85	109
Reabilitare		ml	74	94	
Statie pompare apa uzata	Noua	buc	52,272	66,569	
	Reabilitare	buc	31,363	39,941	
Lucrari de reabilitare necesare Bacau	Reabilitare	-	4,801,294	6,114,448	
Lucrari de reabilitare necesare Moinești	Reabilitare	-	201,752	256,932	
Sistem SCADA	SCADA	buc	4,000	5,094	
Demolare	Demolare paturi de uscare	mc	51	65	
ALIMENTARE CU APA	Retea alimentare cu apa (conducte, camine vane, bransamente)	Extindere	ml	74	94
		Reabilitare	ml	66	84
	Lucrari de reabilitare necesare Bacau	Reabilitare	-	2,521,667	3,211,343
	Lucrari de reabilitare necesare Moinești	Reabilitare	-	1,220,000	1,553,670
	Lucrari de monitorizare necesare Darmanesti	Reabilitare	-	300,000	382,050
	Lucrari de reabilitare necesare Tg Ocna	Reabilitare	-	686,667	874,471
	Lucrari de reabilitare necesare Buhusi	Reabilitare	-	813,333	1,035,780
	Statie pompare	St. repompare	buc	34,580	44,038
		St. hidrofor	buc	28,950	36,869
		Reabilitare	buc	15,601	19,868
	Statie clorinare	Noua	buc	30,559	38,917
		Reabilitare	buc	21,713	27,652
	Instalatie dezinfectie cu UV	Noua	buc	35,000	44,573
	Instalatie corectie duritate	Noua	buc	15,000	19,103
	Statie tratare	Deferizare/ demanganizare	Euro/l/s	17,100	21,777
		Reabilitare STA	Euro/l/s	9,409	11,983
	Foraje noi	20 - 50 m	buc	29,916	38,099
		> 50 m	buc	36,590	46,598
	Reabilitare foraje	20 - 50 m	buc	11,982	15,260
		> 50 m	buc	14,636	18,639
	Captare izvor	nou	buc	21,150	26,935
		100 mc	buc	29,723	37,852
	Rezervor	300 mc	buc	49,538	63,087
400 mc		buc	64,013	81,521	
500 mc		buc	77,523	98,726	
600 mc		buc	90,068	114,702	
700 mc		buc	101,488	129,245	
800 mc		buc	112,023	142,661	
900 mc		buc	121,512	154,746	
1000 mc		buc	130,036	165,601	
Reabilitare 400 mc		buc	22919	29,188	
Reabilitare 500 mc		buc	28629	36,460	
Laborator	Laborator STA	buc	85,000	108,248	
Refulare apa canal	Conducta apa - canal	Extindere	ml	65	83